BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division

Schedule - B

Indent No: BBMP/2023-24/RD/WORK_INDENT727/CALL-4

NAME OF WORK: Filling of Potholes in Ward No.15, Kammagondanahalli, Ward No. 16, Mallasandra, Ward No.17, Chikkasandra, Ward No.18, Bagalagunte , Ward No.19, T. Dasarahalli, Ward No. 20, Nelagedaranahalli, Ward No.21, Chokkasandra, Ward No.22, Peenya Industrial area, Ward No.23, Rajagopalanagara, Ward No.24, Hegganahalli and Ward No.25, Sunkadakatte in Dasarahalli Division, Dasarahalli Zone. (11 works) call-04

Sl. No	Description of work	Unit	Qty	Rate quoted by the contractor Sri. VENKATESH MARAPPANAIDU SUBBADRAMMA(M S V CONSTRUCTIONS COMPANY)	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, Including all lead and lift, loading and unloading, hire charges of machinery and equipments, transportation chargers labour charges and all other incidental charges etc., complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Sqm	14868.27	448.75	Rupees Four Hundred Forty Eight and Seventy Five Paise Only

19/8/24
RECD

Signature of the Contractor

K. M. Halli

Executive Engineer
Dasarahalli Division

Sl. No	Description of work	Unit	Qty	Rate quoted by the contractor Sri. VENKATESH MARAPPANAIDU SUBBADRAMMA(M S V CONSTRUCTIONS COMPANY)	
				In Figures (Rs.)	In Words (Rs.)
2	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. Wet Mix Macadam (Plant mix method) . Including all lead and lift, loading and unloading, hire charges of machinery and equipments, transportation chargers labour charges and all other incidental charges etc., complete as per standard technical detailed specification and design and direction of the Engineer-in-Charge of the work.	Cum	2501.36	2620.30	Rupees Two Thousand Six Hundred Twenty and Thirty Paise Only

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Enginee
Dasarahalli Divisio